

# **RUSTIC HERRINGBONE SPECIFICATION SHEET**









Amulet

Artefact Collection Engineered T&G herringbone by Forté. 15mm thick, 135mm wide, 600mm length. Direct stick installation method onto substrate. Rustic grade, reactive stain, pre-finished with Bona® Matte Lacquer

### PRODUCT DETAILS

Collection Artefact

Engineered Herringbone **Product Type** 

Availability **Custom Order** 

**Total Thickness** 15<sub>mm</sub> Width 135mm Length 600mm

Wear Layer 4mm Solid European Oak

Core Birch Plywood Construction 2-layer Engineered

Re-sands Up to 2 (approx. 1mm removed per

re-sand)

Surface Texture Brushed **Surface Sheen** Matte

Bevel Bevel 4 sides (1.2mm all sides)

Status Pre-finished

(no additional coats required)

**Finish** Reactive stain with Bona® Matte

Lacquer (6 coats)

**Species** European Oak

**Wood Grade** Rustic (refer page 2 for details) Filler Colour Dependant on colour, visit

forte.co.nz for accurate filler colour

The Artefact Collection is also available in 220mm planks, matching stair nosings, chevron, trapezoid, divergent and versailles patterns.

### WARRANTY

For terms and conditions see 10 Year Commercial 25 Year Residential www.forte.co.nz/warranties

### SUSTAINABILITY

FSC® Certified | Low VOC No added Formaldehyde

### INSTALLATION

Installation Method Glue down

(Double Stick for Multi-level) Suitable Substrates Plywood, Particle Board, Concrete,

existing timber - enquire for others

Joint Profile Tongue and Groove (4 sides)

**Suitable Applications** Flooring, Walls, Ceilings

Suitable Uses Residential homes, hospitality, retail

stores, restaurants, apartments

**Underfloor Heating** Hydronic Systems

> · Electric Systems set in screed (ensure screed suitable for UFH) -

enquire for others

Wet Area Suitability Contact the Forté team for information

0508 35 66 77

# TECHNICAL SPECIFICATIONS

Reaction to Fire (Floors) Awaiting test results

Reaction to Fire (Walls

and Ceilings) Awaiting test results

Formaldehyde Emission

AS/NZS 2098.11 E1 (0.03mg/L) 650-700kg/m<sup>3</sup> Wear Layer Density

Slip Ratings

AS/NZS 4586 Wet Test Classification F. Mean COF 0.55 AS/NZS 4586 Dry Test Classification X, Pendulum Mean 42

SRV

### PACK INFORMATION

1.944m<sup>2</sup> Pack Size **Pack Weight** 

Pieces per pack 24 (12 left pieces + 12 right pieces)

# **Plank Profile**

ARTEFACT PLANK

Image Coming Soon

# ARTEFACT - RUSTIC GRADE



An Artefact Rustic grade plank will contain natural colour and structural variation. This grade allows for more frequent, extreme knots and sapwood and discolouration will be expected throughout the planks. Patched knots and cracks will be present and are finished with filler dependent on the products colour.

# **Care and Maintenance**

#### RESIDENTIAL AND COMMERCIAL CARE AND MAINTENANCE

Forté's Product Specialists have collated our care and maintenance recommendations to ensure your flooring looks like new for years to come. Residential and Commercial projects require different levels of care and maintenance. Visit www.forte.co.nz/careandmaintenance

# Warranty

# ARTEFACT 25 YEAR RESIDENTIAL WARRANTY

The Afterfact Collection comes with a full 25 year Residential Warranty. For full warranty terms and conditions, please visit www.forte.co.nz/warranties

## ARTEFACT 10 YEAR COMMERCIAL WARRANTY

The Afterfact Collection comes with a full 10 year Commercial Warranty. For full warranty terms and conditions, please visit www.forte.co.nz/warranties

# **Installation**

# THE ARTEFACT COLLECTION MUST BE INSTALLED BY A TRAINED PROFESSIONAL

Please ensure that you have read and understood the installation guidelines before proceeding to install Afterfact timber flooring. If you have any questions or concerns, please call the Forté technical team on 0508 35 66 77. Failure to adhere to the Forté Installation Guidelines may void your warranty.

For full installation guidelines, please visit www.forte.co.nz/installation